

Name of Work: Periodic Maintenance programme works at Ch. 0+000 to 7+630 of Pabna Town Road (Bus-Terminal to Gaspara) Road under Pabna Road Division during the year 2017-2018.

Summary of Estimate

Item Code	Item Description	Unit	Quantity	Rate	Amount
01/02/04	Provision, maintenance and removal of Sign boards.	L.S.	1.00	8849.00	8849.00
01/02/07	Progress photographs	Month	6.00	1000.00	6000.00
01/03/01	Provide and remove site laboratory and Equipment	L.S.	1.00	331843.00	331843.00
01/03/02	Maintain site laboratory	Month	6.00	7699.00	46194.00
02/10/01	Construction of soil Earthen Shoulders	Cum.	3801.00	259.00	984459.00
03/01/01	Scarify, mix and recompact existing Pavement.	Sqm.	29820.00	48.00	1431360.00
03/03/01	Aggregate base type-I	Cum.	4934.50	6566.00	32399927.00
03/06/01a	Bituminous prime coat (plant placed)	Sqm.	29820.00	123.00	3667860.00
03/07/01a	Bituminous tack coat (plant work)	Sqm.	83435.10	46.00	3838014.60
03/10/01b	Dense Bituminous surfacing -base course (Plant Method) (Bitumen Grade 60/70)	Cum.	2087.40	19906.00	41551784.40
03/10/02b	Dense Bituminous surfacing - Wearing course (Plant Method) (Bitumen Grade 60/70)	Cum.	5245.75	20118.00	105533998.50
03/11/01	Premix Bituminous Carpeting	Cum.	308.61	16224.00	5006888.64
03/13/01	Brick on End Edging	Lin. M.	4200.00	103.00	432600.00
06/03/03	Concrete Side Ditch/U Drain	Lin. M.	360.00	8867.00	3192120.00
06/05/01	Road Marking -Thermoplastic material	Sqm.	3742.40	1069.00	4000625.60
06/10/01	Traffic Sings	Number	20.00	6901.00	138020.00
06/10/02	Sign Post	Number	20.00	3073.00	61460.00
Special 01	Construction of Concrete barrier/ divider	Lin. M.	985.00	5535.00	5451975.00
				Total	208083978.74

TR: 20, 80, 80, 170/150
74-5
2076/26

(মোঃ বখতিয়ার আলম)
উপ-বিভাগীয় প্রকৌশলী, সড়ক (আ.স.স.)
সড়ক উপ-বিভাগ-১, পাবনা।

(মোঃ হাবিবুর রহমান)
উপ-সহকারী প্রকৌশলী, (অঃ দাঃ) সওজ,
সরকারি বিদ্যুৎ পাবনা।

(মোঃ সাদিকুর রহমান)
সহকারী প্রকৌশলী, সওজ (চঃ দাঃ)

পরিচিতি নং- ০০৫০৯৯
নির্বাহী প্রকৌশলী, সড়ক
সড়ক বিভাগ, পাবনা।