




Summary of Engineer's Estimate

Item Code	Item Description	Qty.	Unit	Unit Rate	Total Amount
1	2	3	4	5	6
01/02/07	Progress Photographs	6.00	Month	1000.00	6,000.00
01/03/01	Provide and Remove Site Laboratory & Equipment	L.S.	L.S.	331843.00	331,843.00
01/03/02	Maintain Site Laboratory	6.00	Month.	7699.00	46,194.00
Sub Total (A) =					384,037.00
02/02/03	Roadway excavation in existing pavement (Not reinforcement concret).	821.10	Cum.	265	217,591.50
02/06/02	Embankment fill from borrow pit in contracot's arranged land.	1925.00	Cum.	309.00	594,825.00
02/10/01	Construction of Soil Earthen Shoulders.	5535.00	Cum.	259.00	1,433,565.00
Sub Total (B) =					2,245,981.50
03/01/01	Scarify, Mix and recompact existing pavement and/or shoulder	86075.00	Sqm.	48.00	4,131,600.00
03/02/01	Sub Base.	275.00	Cum.	4361.00	1,199,275.00
03/03/01	Aggregate Base Type-I	12911.25	Cum.	6566.00	84,775,267.50
03/06/01(a)	Bituminous Prime Coat (Plant Placed)	86075.00	Sqm.	123.00	10,587,225.00
03/10/02(b)	Dense Bituminous Surfacing - Wearing course (Plant Method) (Bitumen Grade 60/70).	4303.75	Cum.	20118.00	86,582,842.50
03/13/01	Brick on End Edging	31300.00	L.M	103.00	3,223,900.00
Sub Total (C) =					190,500,110.00
05/05/01	Road Marking - Thermoplastic Material (indicate if screed or spray application)	782.50 626.50	Sqm.	1069.00	936,492.50 6,69,194.00
05/10/01	Traffic Signs	25.00	Nos.	6901.00	172,525.00
05/10/02	Sign Post	25.00	Nos.	3073.00	76,825.00
05/15/01	Concrete Guide Post (1.6 m Long, 200mm Dia)	50.00	Nos.	2068.00	103,400.00
05/16/01	Concrete Km Post.	16.00	Nos.	8656.00	138,496.00
05/17/01(a)	RCC palasiding (4m post x 200mm x 200mm)	550.00	L. M.	10037.00	5,520,350.00
Sub Total (D) =					6,848,088.50
Sub Total (A+B+C+D) =					199,978,217.00
					19,98,10,918/5
02/02/06	Deduction of value of materials recovered from existing road pavement.	821.10 821.50	Cum.	-2212.00	-1,816,273.20 -18,16,052.00


(A.H.M. Mahmud Hassan)
Sub Asstt. Engineer, RHD-3,
Road Sub-Division-1, Khulna.


(S. M. Amzad Hossain)
Sub Divisional Engineer, (C.C) RHD,
Road Sub-Division-1, Khulna.


(Md. Abul Kalam Azad)
Executive Engineer, (C.C.), RHD,
Road Division, Khulna.

Signed
A.H.M.
কাজী আব্দুল আল-মাহমুদ
সহকারী প্রকৌশল
পটল পরিদপ্তর ও মহাপ্রকৌশল বিভাগ
পটল পরিদপ্তর ও পটল মহাপ্রকৌশল
পটল পরিদপ্তর ও পটল মহাপ্রকৌশল

প্রাক্কলিত ক্রয় টাকা ১৯,৯৮,২০,৯২৮/৫ (ড্রেনিং মোর্চি আটান্ডাই ১৯৯৮
৮ম হাজার নম্বর আটান্ডো এবং দশম পাঁচ) মাত্র অনুমোদন করা হল।

১২০২
২৭/১২/১৭
(বনশ্রী মজুমদার)
উপ-সহকারী প্রকৌশলী সওজ
খুলনা জোন, খুলনা।

২৭/১২/১৭
সহকারী প্রকৌশলী (সওজ)
খুলনা জোন, খুলনা।

(মোঃ রুহুল আমীন)
অতিরিক্ত প্রধান প্রকৌশলী, সওজ
(চলতি দায়িত্ব)
খুলনা জোন, খুলনা।

Signed
AAM
কাজী আব্দুল্লাহ আল-মামুন
প্রোগ্রামার
নতুন পরিদপন ও মহাপ্রকল্প বিভাগ
নতুন পরিদপন ও সেতু মহাপ্রকল্প
গণপ্রজাতন্ত্রী বাংলাদেশ সরকার