

Name of Work: Dense Bituminous Surfacing work from Ch: 41+169 to Ch 52+069 (Charavita to Hamidpur) with 2.550 km Strengthening of Bhatipara-Kalna-Lohagara-Narail-Jessore Road (N-806) and Ch. 0+000 to Ch. 4+330 (Charavita to Bagherpara Bazar) with 1.105 km Strengthening of Bagherpara Link Road (Z-7501) under Periodic Maintenance Programme (PMP-Road) of Road Division Jessore during the year 2017-2018.

Compile Estimate Summary Sheet

Item Code No.	Description	Quantity		Total Qty (a+b)	Unit	Rate	Amount
		N-806(a)	Z-7501(b)				
01/02/04	Provision, Maintenance and Removal of Sign Boards.	1.00	0.00	1.00	L.S	8849.00	8849.00
01/02/07	Progress of Photograph.	6.00	0.00	6.00	Month	1000.00	6000.00
01/03/01	Provide & Remove Site Laboratory & Equipment.	1.00	0.00	1.00	L.S	331843.00	331843.00
01/03/02	Maintain Site Laboratory.	6.00	0.00	6.00	Month	7699.00	46194.00
01/03/03	Special or Additional Test	1.00	0.00	1.00	Pro.sum	60000.00	60000.00
02/10/01	Construction of Soil Earthen Shoulder.	6503.4	2400.00	8903.40	Cum	259.00	2305980.60
03/01/01	Scarify Mix and Recompect Existing Pavement	16125	23661.00	39786.00	Sqm	48.00	1909728.00
03/01/02	Repair of Potholes on the Existing Pavement.	113.97	0.00	113.97	Cum	15733.00	1793090.01
03/03/01	Aggregate Base Type-I	2418.75	911.63	3330.38	Cum	6566.00	21867275.08
03/06/01a	Bituminous Prime Coat (Plant Placed)	16125.0	23661.00	39786.00	Sqm	123.00	4893678.00
03/07/01a	Bituminous Tack Coat (Plant work)	67889.65	23815.00	91704.65	Sqm	46.00	4218413.90
03/10/01b	Dense Bituminous Surfacing-Base Course (Plant Method)	806.25	1183.05	1989.30	Cum	19906.00	39599005.80
03/11/01.	Premix Bituminous Carpeting (Crack and Undulation repair by Carpetinh method)	291.98	0.00	291.98	Cum	16224.00	4737083.52
03/10/02b	DBS- wearing Course 50mm thick (Av.) <i>(P. method Bitumen grade 60/70)</i>	3102.50	952.60	4055.10	Cum	20118.00	81580501.80
03/13/01.	Brick on Edging.	5100.0	8604.00	13704.00	Lin.m	103.00	1411512.00
06/05/01	Road Marking - Thermoplastic Material indicate if seccred or spray application.	2694.00	208.40	2902.40	Sqm	1069.00	3102665.60
06/10/01	Traffic Signs.	10.00	9.00	19.00	No.	6901.00	131119.00
06/10/02	Sign Post.	10.00	9.00	19.00	No.	3073.00	58387.00
06/16/01	Concerete Kilometer Post (As per drawing)	11.00	5.00	16.00	No.	8656.00	138496.00
Total Tk=						168199822.31	

(Md. Mehedi Hasan)
Sub-Assistant Engineer, RHD
Road Sub-Division-2, Jessore.

(Al-Imran)
Sub-Assistant Engineer, RHD
Road Circle, Jessore.

(Ali Noor Ahle)
Sub-Divisional Engineer, RHD
Road Sub-Division-2, Jessore.

(Syed Shafiqun Nabi)
Assistant Engineer, RHD
Road Circle, Jessore.

(Md.Zahangir Alam)
Executive Engineer, RHD
Road Division, Jessore.

(Md.Suruz Mia)
Superintending Engineer, RHD (C.C)
Road Circle, Jessore.

Signed
AAM
কাজী আব্দুল আল-মামুন
সিনিয়র ইঞ্জিনিয়ার
পল্লী পরিদপ্তর ও মহাসড়ক বিভাগ
সড়ক পরিদপ্তর ও সেতু মহাপরিদপ্তর
গণপ্রজাতন্ত্রী বাংলাদেশ সরকার

প্রস্তুতকৃত প্রকৃতি: ২৫৮৯, ১৯, ৮২২/১০২ (প্রধান কোর্ট বিচারিক দপ্তর
নিবন্ধনকারী শাস্ত্রীর আদেশের মাধ্যমে এবং প্রকৃতি প্রকৃতি
আজ প্রকৃতি প্রকৃতি প্রকৃতি প্রকৃতি

১২/০৭/১৭

সিইকারী প্রকৃতি (সংজ্ঞা)
প্রকৃতি প্রকৃতি, প্রকৃতি

১২/০৭/১৭
(মোঃ রহিম আলী)
অতিরিক্ত প্রধান প্রকৃতি, সওদ
(চলতি দায়িত্ব)
প্রকৃতি প্রকৃতি, প্রকৃতি

Signed

AAH

কাজী আব্দুল আল-মামুন
প্রকৃতি প্রকৃতি
প্রকৃতি প্রকৃতি ও প্রকৃতি প্রকৃতি
প্রকৃতি প্রকৃতি ও প্রকৃতি প্রকৃতি
প্রকৃতি প্রকৃতি ও প্রকৃতি প্রকৃতি