

OFFICIAL COST ESTIMATE.

Name of Work : DBS Wearing Course at Ch: 00+000 (Chaulia Bus Stand) to Ch: 09+300 (Dholhara Bazar) & Ch: 26+165 (Polita) to Ch: 30+930 (Monokhali) of Magura-Narail (R-720) Road under Road Division, Magura during the year 2017-2018.

Working Length Ch: 00+000 to Ch: 09+300 = 9300.00 m
 Ch: 26+165 to Ch: 30+930 = 4765.00 m
 = 14065.00 m

Division-1-General & Site Facilities


Item Code	Description of Item & Measurement	Qty	Unit	Unit Rate	Amount
01/01/01	Maintenance and Protection of Traffic	1.00	LS	80,257.00	80,257.00
01/02/04	Provision and Maintenance and removal of Sign Board	1.00	LS	8,849.00	8,849.00
01/02/07	Progress Photographs	6.00	Month	1,000.00	6,000.00
01/03/01	Provide and Remove Site Laboratory & Equipment	1.00	LS	331,843.00	331,843.00
01/03/02	Maintain Site Laboratory	6.00	Month	7,699.00	46,194.00
Sub-Total =					473,143.00

Division-2-Earthwork

Item Code	Description of Item & Measurement	Qty	Unit	Unit Rate	Amount
02/10/01	Construction of Soil Earthen Shoulders				
	1+000 9+300 = 8300.00 m				
	26+165 30+930 = 4765.00 m				
	= 13,065.000 m				
	2 x 13065.00 x 1.300 x 0.300 = 10190.70 cum	10,190.70	Cum	259.00	2,639,391.30
Sub-Total =					2,639,391.30

Division-3-Pavemen Works

03/07/01(a)	Bituminous Tack Coat (Plant Work)				
	For Profile Correction				
	00+100 2+200 = 2100.00 m				
	2100.00 x 7.300 = 15330.00 sqm				
	4+250 6+000 = 1750.00 m				
	1750.00 x 5.500 = 9625.00 sqm				
	6+800 9+000 = 2200.00 m				
	2200.00 x 5.500 = 12100.00 sqm				
	26+590 28+250 = 1660.00 m				
	1660.00 x 5.500 = 9130.00 sqm				
	Sub-Total = 46185.00 Sqm				
	Befor Wearing Course				
	00+300 2+220 = 2220.00 m				
	2220.00 x 7.300 = 16206.00 sqm				
	2+220 9+300 = 7080.00 m				
	7080.00 x 5.500 = 38940.00 sqm				
	26+165 30+930 = 4765.00 m				
	4765.00 x 5.500 = 26207.50 sqm				
	Sub-Total = 81353.50 Sqm				
	Total = 127538.50 Sqm	127,538.50	Sqm	46.00	5,868,771.00

Signed


কাজী আবদুল্লাহ আল মামুন
 নির্মিত প্রকল্পের
 সড়ক পরিবহন ও মহাসড়ক বিভাগ
 সড়ক পরিবহন ও সেতু মন্ত্রণালয়
 গণপ্রজাতন্ত্রী বাংলাদেশ সরকার

03/01/01	Premix Bituminous Carpeting (for Profile correction)									
	For Profile Correction									
00+100	2+200	=	2100.00	m						
			2100.00	x 7.300	x 0.040	=	613.20	Cum		
4+250	6+000	=	1750.00	m						
			1750.00	x 5.500	x 0.040	=	385.00	Cum		
6+800	9+000	=	2200.00	m						
			2200.00	x 5.500	x 0.040	=	484.00	Cum		
26+590	28+250	=	1660.00	m						
			1660.00	x 5.500	x 0.040	=	365.20	Cum		
			Sub-Total			=	1847.40	Cum		
							1,847.40	Cum		
								16,224.00		
									29,972,217.60	
03/10/02(b)	Dense Bituminous Surfacing Wearing Course (Plant Method) (Bitumen Grade 60/70)									
00+000	2+220	=	2220.00	m						
			2220.00	x 7.300	x 0.050	=	810.30	Cum		
2+220	9+300	=	7080.00	m						
			7080.00	x 5.500	x 0.050	=	1947.00	Cum		
26+165	30+930	=	4765.00	m						
			4765.00	x 5.500	0.050	=	1310.38	Cum		
			Sub-Total			=	4067.68	Cum		
							4,067.68	Cum		
								20,118.00		
									51,833,586.24	
								Sub-Total	=	117,672,574.84
								Total (Division : 1 + 2 + 3)	=	120,785,109.14

(Md. Kafi Hossain)
Sub-Assistant Engineer, RHD
Road Sub-Division, Magura

(Md. Badsha Miya)
Sub-Assistant Engineer, RHD
Road Division, Magura

(Md. Abdullah Baki)
Sub-Divisional Engineer C.C. RHD
Road Sub-Division, Magura

(Md. Nazrul Islam)
Executive Engineer C.C. RHD
Road Division, Magura

উপ-সহকারী প্রকৌশলী (সওজ)
সড়ক সার্কেল, যশোর।

সহকারী প্রকৌশলী (সওজ)
সড়ক সার্কেল, যশোর।

উপসহকারী প্রকৌশলী (সওজ)
সড়ক সার্কেল, যশোর।

প্রকল্পের ব্যয় টাকা ২২০৭,৮৫,০০০/০০ (দুই কোটি দুই লাখ পঁচাত্তর হাজার
একশত নয় টাকা মাত্র) এবং অন্যান্য ব্যয় করা হইবে।

(বনদ্রী মজুমদার)
উপ-সহকারী প্রকৌশলী সওজ
খুলনা জোন, খুলনা।

মোঃ রমজান আলী
সহকারী প্রকৌশলী, সওজ
খুলনা জোন, খুলনা।

মোঃ জর্জিস হোসেন)
অতিরিক্ত প্রধান প্রকৌশলী, সওজ
(চলতি দায়িত্ব)
খুলনা জোন, খুলনা।

Signed
AAH
কাজী আবদুল্লাহ আল মামুন
সিনিয়র জেএমএস
সড়ক পরিবহন ও সড়কপথ বিভাগ
সড়ক পরিবহন ও সড়ক সড়কপথ
নগরসংস্কারী বাংলাদেশ সরকার