

Items of Work: Overlay works (DBSW) under Periodic Maintenance Programme (PMP) of Sathkira-(Sakhipur)Debhata Road (Z-7607) at
 Estimate : 00+000 to 5+423 under Road Division, Sathkira during the year 2017-2018.

Bill Of Quantity.

Section: 01 General & Site Facilities.

Item Code	Item Description	Quantity	Unit	Rate (Taka)	Amount(Taka).
110101	Supply, Erect and Remove Field Office for Engineer	1.00	L.S	249,497.00	249,497.00
110104	Provision, Maintenance and Removal of Sign Boards	1.00	L.S	8,849.00	8,849.00
110107	Progress Photographs	8.00	Month	1,000.00	8,000.00
110108	Provide and Remove Site Laboratory & Equipment	1.00	L.S	331,843.00	331,843.00
110109	Maintain Site Laboratory	8.00	Month	7,699.00	61,592.00
Sub-Total:01					659,781.00

Section: 02 Earth Work.

Item Code	Item Description	Quantity	Unit	Rate (Taka)	Amount(Taka).
210101	Roadway excavation in existing Pavement (not reinforce concrete)	1,223.46	Cum	265.00	324,216.90
210102	Embankment fill from borrow pit in contractor's Arranged land	10,097.00	Cum	309.00	3,119,973.00
Sub-Total:02					3,444,189.90

Section: 03 Pavement Work.

Item Code	Item Description	Quantity	Unit	Rate (Taka)	Amount(Taka).
310101	Scally, Mix and Recompact Existing Pavement and/or Shoulder	29,771.50	Sqm	48.00	1,429,032.00
310102	Aggregate Base Type-I	5,954.30	Cum	6,566.00	39,095,933.80
310103	Aggregate Base Type-II	2,200.00	Cum	4,732.00	10,410,400.00
310104	Bituminous Prime Coat (Plant Placed)	29,771.50	Sqm	123.00	3,661,894.50
310105	Bituminous Tack Coat (Plant Work)	29,958.50	Sqm	46.00	1,378,091.00
310106	Dense Bituminous Surfacing-Base Course (Plant Method)	1,495.18	Cum	19,906.00	29,763,053.08
310107	Dense Bituminous Surfacing - Wearing Course (Plant Method)	1,497.93	Cum	20,118.00	30,135,355.74
310108	Bitumen Grade 60/70)				
310109	Brick on End Edging	10,850.00	Lin.M	103.00	1,117,550.00
Sub-Total: 03					116,991,310.12

Signed
 AASUN
 কাজী আবদুল্লাহ আল মামুন
 নির্মিতা প্রকল্প
 সড়ক পরিবহন ও মহাসড়ক বিভাগ
 সড়ক পরিবহন ও সেতু মন্ত্রণালয়
 গণপ্রজাতন্ত্রী বাংলাদেশ সরকার

Division: 06 Incidentals.

Item Code	Item Description	Quantity	Unit	Rate (Taka)	Amount (Taka)
06/05/01	Road Marking - Thermoplastic Material (indicate if screed or spray application)	216.92	Sqm	1,069.00	231,887.48
06/10/01	Traffic Signs	10.00	Nos	6,901.00	69,010.00
06/10/02	Sign Post	10.00	Nos	3,073.00	30,730.00
06/16/01	Concrete Kilometer Post (As per drawing)	6.00	Nos	8,656.00	51,936.00
06/17/01(a)	RCC Palisading (4m Post, 200mm x 200mm)	100.00	Lin.m	10,937.00	1,093,700.00
Sub-Total, 06 =				1,387,263.48	
Grand Total: =				122,482,544.50	

Deduction Items

(Signature)
20/09/21
(Syed Gias Uddin)
Sub-Divisional Engineer(AC), RHD
Road Sub - Division - 2 Satkhira.

Item Code	Unit	Rate	Amount in Tk
02/02/04	Cum	22128	2707488.00
Deduction of value materials recovered from existing Road Pavement.			
		1223.46	1224.00
		1224.00	
Total = - 2707488.00			

(Signature)
20/09/21
(Md. Kamruzzaman)
Sub Assistant Engineer, RHD
Road Sub - Division - 2, Satkhira

(Signature)
20/09/21
(Md. Kamrul Sheikh)
Sub Assistant Engineer(AC) RHD
Road Division, Satkhira.

(Signature)
20/09/21
(Md. Ziauddin)
Assistant Engineer, RHD
Road Division, Satkhira.

(Signature)
20/09/21
(Md. Monzurul Karim)
Executive Engineer (C.C), RHD
Road Division, Satkhira.

(Signature)
20/09/21
(মোহাম্মদ মুজিবুল আলী)
উপ-সহকারী প্রকৌশলী, সড়ক
সড়ক সার্কেল, ফুলনা।

(Signature)
20/09/21
(সনৎ কুমার সাহা)
সহকারী প্রকৌশলী (সি.এস.এস) সড়ক
সড়ক সার্কেল, ফুলনা।

(Signature)
20/09/21
(গোঃ জাকির হোসেন)
কর্তৃপক্ষ প্রকৌশলী (সি.এস.এস) সড়ক
সড়ক সার্কেল, ফুলনা।

Signed
AASIN
কাজী আবদুল্লাহ আল মামুন
সিনিয়র জে.এম.এস.
সড়ক পরিবহন ও মহাসড়ক বিভাগ
সড়ক পরিবহন ও সেতু মন্ত্রণালয়
গণপ্রজাতন্ত্রী বাংলাদেশ সরকার

Stream code 02/02/06; প্রবর্তন ছালাচরণের বার্ষিক ঠিকানা ২৭, ০৭৪৬৬-১০০ যা
 প্রকাশনার দিন হতে বর্তন করিতে হবে।
 আনুমানিক ১২, ২৪, ৬২, ৬৪৪/৬০ (যদি কোন চেষ্টা না হয় বিবরণ
 সহকারী সাংসদ প্রতিনিধিত্ব সহ; সাংসদ সচিব) অন্য অঙ্গের বাক্য হলো।

১১/০৭/১৪

(বন্যী মহাসচিব)
 উপ-সহকারী প্রকৌশলী, সওজ
 খুলনা জোন, খুলনা।

১১/০৭/১৪

স্বঃ রুমজান আলী
 সহকারী প্রকৌশলী, সওজ
 খুলনা জোন, খুলনা।

১১/০৭/১৪

(স্বঃ জর্জিস হোসেন)
 অতিরিক্ত প্রধান প্রকৌশলী, সওজ
 (চলতি নথি)
 খুলনা জোন, খুলনা।

Signed
 AAN
 কাজী আবদুল্লাহ আল মামুন
 নির্মিত প্রকৌশলী
 সওজ পরিদপ্তর ও মহানগর বিভাগ
 সওজ পরিদপ্তর ও সওজ মহানগর
 নন্দলাভাভী বাংলাদেশ সরকার